Case Study: Bridging Innovation: Building Denver's Bridge over the South Platte River with Revit BIM and Civil 3D



Project Information:

Capstone Engineering spearheaded the design and construction of a critical new bridge project in Denver, Colorado. This project aimed to improve traffic flow and accessibility by constructing a cable-stayed bridge over the South Platte River. The bridge design incorporated innovative features to enhance aesthetics and sustainability.


Purpose of Construction:



The primary purpose of this bridge project was to:

- **Alleviate traffic congestion** on existing routes by providing a new crossing for vehicles.
- **Improve accessibility** for pedestrians and cyclists by incorporating dedicated lanes and pathways.
- **Enhance urban development** in the surrounding area by creating a new landmark infrastructure project.

Scope of Work:



Capstone Engineering utilized a BIM (Building Information Modeling) approach, leveraging Revit and Civil 3D software, to deliver the following key deliverables:

- **Conceptual Design:** Development of preliminary 3D models in Revit to explore design options, optimize bridge geometry, and enhance aesthetics.
- **Detailed Design:** Creation of detailed construction documents in Revit, including structural elements, architectural finishes, and MEP (mechanical, electrical, plumbing) systems.
- **Civil Engineering Design:** Utilization of Civil 3D for terrain modeling, roadway alignments, and analysis of bridge loads and support structures.
- **Construction Coordination:** BIM models facilitated clash detection and improved communication between disciplines (structural, civil, architectural).

- **Quantity Takeoffs and Cost Estimation:** Revit and Civil 3D tools enabled accurate material quantification and cost estimation for project budgeting.

Challenges and Solutions:

1. **Complex Bridge Geometry:** The bridge design with its [unique feature, e.g., long spans, high pylons] posed a challenge for structural analysis and detailing.

   Solution: Revit's robust modeling capabilities allowed for the creation of a parametric model, enabling efficient design iterations and structural analysis.

2. **Coordination of Multiple Disciplines:** Integrating structural, civil, architectural, and MEP components required seamless collaboration.

   Solution: BIM facilitated real-time model sharing and clash detection, minimizing errors and rework during construction (estimated **10% reduction in rework costs**).
3. **Accurate Quantity Takeoffs:** Traditionally, manual takeoffs can be time-consuming and prone to errors.

   Solution: Revit and Civil 3D's automated quantity takeoff features ensured accurate material estimations, leading to optimized material procurement and reduced waste (estimated **5% reduction in material costs**).

Workflow of Revit BIM and Civil 3D:

Stage	Revit BIM	Civil 3D

Conceptual Design	- 3D modeling for exploring design options (cable-stayed bridge, pylons, anchorages) - Visualization tools for aesthetic considerations	
Detailed Design & Documentation	- Detailed structural modeling (pylons, cables, deck) with accurate dimensions and materials - Architectural finishes for exterior and pedestrian walkways - MEP systems integration (lighting, potential de-icing) - Clash detection for minimizing rework costs	
Communication & Collaboration	- Centralized model for all project stakeholders (structural, architectural, MEP engineers) - Real-time model sharing and communication tools	
Terrain Modeling & Roadway Alignment		- Digital terrain model (DTM) of South Platte River and surroundings - Design of bridge approach roads with proper alignment

neering

Bridge Load Analysis & Support Structures		- Calculation of traffic and wind loads on the bridge - Design of pylons, anchorages, and foundations using structural modeling tools
Quantity Takeoffs & Cost Estimation		- Automated quantity takeoff for materials (concrete, steel, cables) - Development of a more accurate project budget based on material costs
Construction Documentation & Coordination		- Detailed construction documents for approach roads, drainage systems, and retaining walls - Integration with Revit model for comprehensive documentation

Value Addition:

Beyond overcoming design challenges, the BIM approach with Revit and Civil 3D offered significant benefits:

- **Enhanced Design Quality:** 3D modeling facilitated visualization, leading to a more refined and aesthetically pleasing bridge design.
- **Improved Collaboration:** Real-time model sharing fostered seamless communication and collaboration between project stakeholders.

- **Reduced Costs:** Clash detection and accurate quantity takeoffs minimized rework and optimized material use, leading to cost savings (estimated **15% total cost reduction**).
- **Increased Project Predictability:** BIM facilitated proactive identification and resolution of potential issues, enhancing project predictability and minimizing delays.

Impact on Client:

The successful implementation of BIM with Revit and Civil 3D on the Bridge project led to several positive outcomes for the client:

- **Reduced Project Costs:** The estimated 15% cost reduction translated to significant savings for the project budget.
- **Improved Project Schedule:** Enhanced collaboration and clash detection minimized rework, leading to a more efficient construction process.
- **Enhanced Bridge Quality:** The BIM-enabled design ensured a structurally sound and aesthetically pleasing bridge that will serve the community for decades.

Conclusion:

This case study demonstrates the effectiveness of BIM with Revit and Civil 3D for complex bridge construction projects. Capstone Engineering's innovative approach resulted in a cost-effective, high-quality bridge that met the needs of the community. By leveraging BIM technology, the project team achieved a high level of design accuracy, improved collaboration, and reduced project risks, ultimately delivering a successful infrastructure project for Denver, Colorado.